

# MASON COUNTY ROAD COMMISSION

## Board of Commissioners

Douglas Robidoux, Chairman  
Bill Schwass, Vice-Chairman  
Nick Matiash, Member  
Wayne A. Schoonover, P.E., Manager/Director

510 E. State St.  
PO Box 247  
Scottville MI 49454-0247  
Office: (231) 757-2882 Fax: (231) 757-2662  
e-mail: info@masoncountyroads.com

## PROCESSED AGGREGATE (GRAVEL) MATERIAL:

Sealed bids will be received at the office of the Mason County Road Commission at 510 East State Street, Scottville, Michigan 49454 until 11:00 A. M., Wednesday, March 7, 2018 for furnishing a minimum of 25,000 cubic yards of aggregate (gravel) material and 10,000 cubic yards of associated ice control sand. Material shall meet current MCRC Standard Specifications, see attached.

## QUANTITY BEING BID

GRAVEL: \_\_\_\_\_ TON / CUBIC YARD (circle one)  
ICE CONTROL SAND: \_\_\_\_\_ TON / CUBIC YARD (circle one)

### Processed Aggregate (Gravel) Material

Delivered F.O.B. Scottville location: \_\_\_\_\_ per TON

### Ice Control Sand Material

Delivered F.O.B. Scottville location: \_\_\_\_\_ per TON

### Processed Aggregate (Gravel) Material

Suppliers Yard/Pit: \_\_\_\_\_ per CUBIC YARD

### Ice Control Sand Material

Suppliers Yard/Pit: \_\_\_\_\_ per CUBIC YARD

Specify Location: \_\_\_\_\_

### PROCESSING in MCRC pit, Irons location:

Aggregate (Gravel) Material: \_\_\_\_\_ per TON

Ice Control Sand Material: \_\_\_\_\_ per TON

Bids must be submitted in a sealed envelope bearing the name of the bidder and plainly marked as to the item in the best interest of the county of Mason.

FIRM BID SUBMITTED BY: \_\_\_\_\_ COMPANY NAME

\_\_\_\_\_ ADDRESS

\_\_\_\_\_

\_\_\_\_\_ PHONE NUMBER

\_\_\_\_\_ EMAIL ADDRESS

signed: \_\_\_\_\_

Closing Date 11:00 A.M. Wednesday, March 7, 2018

MASON COUNTY ROAD COMMISSION  
PROCESSED AGGREGATE (GRAVEL) SPECIFICATIONS

Description

This material shall be used for aggregate surfacing, patching and for aggregate base material under a hard surfacing. It is intended that this material shall be available for a period of at least one (1) year and possible multiple years.

The material may be delivered to the yard of the Mason County Road Commission, depending on the cost of hauling, pickup by the MCRC at the Bidders yard, or produced by the Bidder at the MCRC pit in the Irons, MI. area.

Materials

This material shall be processed, well graded, and homogenous material. It shall consist of clean, hard, durable, course aggregate, free from clay lumps and soft or flaky material and shall conform to the following gradation. Any deviation of this gradation shall only be accepted if approved in writing by the Mason County Road Commission.

Sieve Size	% Passing
1"	100
¾"	90-100
3/8"	65-85
No. 8	30-55
Wash	6-10
Crushed	25% min

Stockpile

Material - on MCRC property - shall be stockpiled in one pile accessible at any time of year.

Stockpile in the Bidders yard shall be secured in an area protected by a gate or fence or other means acceptable by the Mason County Road Commission. The Road Commission shall provide its own means for loading trucks. Stockpile must be available for one (1) to two (2) construction seasons depending on size and/or location of the pile.

Delivery of Materials

If MCRC elects to have material delivered to their yard:

- Delivery of materials may be over an extended period of time, not to exceed one (1) year.
- Scheduling shall be as ordered by MCRC. Upon receipt of order, the successful Bidder(s) shall commence delivery within twenty four (24) hours.

### Testing

Aggregate (Gravel) gradation testing with passing results and Ice Control Sand gradation test results shall be provided by the Bidder(s) prior to final payment. MCRC reserves the right to do periodic independent assurance testing. Material determined to be not in compliance with the gradation may be rejected. Testing frequency shall be one (1) test for each 1000 cubic yards or 1500 tons.

### Measurement and Payment

Measurement for material stockpiled in the suppliers yard shall be by **Cubic Yard**. The supplier shall certify to the amount present and guarantee amount. The MCRC reserves the right to do periodic stockpile cross sections to verify amounts.

Measurement of material delivered to the MCRC property, either the Scottville site or the Irons site, shall be by the **Ton** with the supplier to provide weight tickets from a certified scale for each load.

Payment shall be based on the unit price quoted by the ton or cubic yard whichever is bid and shall include all labor, equipment and miscellaneous other costs to provide the material. No other additions shall be considered in the unit price.

Payment for material either stockpiled or delivered shall be over a minimum period of twelve (12) months - as agreed to by the Mason County Road Commission and the Contractor - beginning the first month after award, then continuing until the amount is paid off.