



MASON COUNTY ROAD COMMISSION

Michael Ingison, Chairman
Jeff Conklin, Vice-Chairman
Deb Del Zoppo, Member

Steve Wessels, Manager/Director
Eric Nelson, County Highway Engineer

NOTICE TO BIDDERS MASON COUNTY ROAD COMMISSION MASON COUNTY, MICHIGAN

The Board of County Road Commissioners of the County of Mason will receive sealed bids at 510 E. State Street, P.O. Box 247, Scottville, Michigan until 11:00 a.m., local time, **Tuesday, March 12, 2024**, at which time the bids will be publicly opened and read for furnishing the following materials and services:

Processed 22A or 22A Modified Aggregate (Gravel) & 2NS Material

Bid Forms and Specifications may be obtained at the office of the Mason County Road Commission. All bids must be submitted in SEALED ENVELOPES bearing the name of the Bidder and appropriately marked as to the item being bid.

The Commission reserves the right to accept any and all bids, in part or entirety; waive any informalities in bids, and to accept the bid, which in their opinion is in the best interest of the Mason County Road Commission and the County of Mason.

The Mason County Road Commission is in compliance with the provisions of Title VI of the Civil Rights Act of 1964 as amended.

BOARD OF MASON COUNTY ROAD COMMISSION

Mike Ingison, Chairman
Jeff Conklin, Vice-Chairman
Deb Del Zoppo, Member

2024 Material Bid Notice

MASON COUNTY ROAD COMMISSION
PROCESSED AGGREGATE (GRAVEL) SPECIFICATIONS

Description

This material shall be used for aggregate surfacing, patching and for aggregate base material under a hard surfacing. It is intended that this material shall be available for a period of at least one (1) year and possible multiple years.

The material may be delivered to the yard of the Mason County Road Commission, depending on the cost of hauling, or pickup by the MCRC at the Bidders yard.

22A-Modified Materials

This material shall be processed, well graded, and homogenous material. It shall consist of clean, hard, durable, course aggregate, free from clay lumps and soft or flaky material and shall conform to the following gradation. Any deviation of this gradation shall only be accepted if approved in writing by the Mason County Road Commission.

Sieve Size	% Passing
1"	100
¾"	90-100
3/8"	65-85
No. 8	30-55
Wash	6-10
Crushed	25% min

22A Materials

This material shall be processed, well graded, and homogenous material. It shall consist of clean, hard, durable, course aggregate, free from clay lumps and soft or flaky material and shall conform to the following gradation. Any deviation of this gradation shall only be accepted if approved in writing by the Mason County Road Commission.

Sieve Size	% Passing
1"	100
¾"	90-100
3/8"	65-85
No. 8	30-50
Wash	4-8
Crushed	25% min

2NS – Ice Control Sand

This material shall be processed, well graded, and homogenous material. The below gradation represents the target gradation for 2NS material. The 3/8, No.4 & No.8 sieve must follow the below requirements. The remaining sieves may vary depending on the quality of the materials excavated from the pit.

Sieve Size	% Passing
3/8"	100
No. 4	95-100
No. 8	65-95
No. 16	35-75
No. 30	20-55
No. 50	10-30
No. 100	0-10
Wash	0-3

Stockpile

Stockpile in the Bidders yard shall be secured in an area protected by a gate or fence or other means acceptable by the Mason County Road Commission. The Road Commission shall provide its own means for loading trucks.

Stockpile must be available for one (1) to two (2) construction seasons depending on size and/or location of the pile.

Delivery of Materials

If MCRC elects to have material delivered to their yard:

- Delivery of materials may be over an extended period of time, not to exceed one (1) year.
- Scheduling of deliveries shall be as ordered by MCRC. Upon receipt of order, the successful Bidder(s) shall commence delivery within twenty-four (24) hours.

Testing

Aggregate (Gravel) gradation testing with passing results and Ice Control Sand gradation test results shall be provided by the Bidder(s) prior to final payment. MCRC reserves the right to do periodic independent assurance testing.

Material determined to be not in compliance with the gradation may be rejected. Testing frequency shall be one (1) test for each 1,000 cubic yards or 1,500 tons.

Measurement and Payment

Measurement for material stockpiled in the supplier's yard shall be by **Cubic Yard**. The supplier shall certify to the amount present and guarantee amount. The MCRC reserves the right to do periodic stockpile cross sections to verify amounts.

Measurement of material delivered to the MCRC property in Scottville shall be by the **Ton** with the supplier to provide weight tickets from a certified scale for each load.

Payment shall be based on the unit price quoted by the ton or cubic yard whichever is bid and shall include all labor, equipment, and miscellaneous other costs to provide the material. No other additions shall be considered in the unit price.

Payment for material either stockpiled or delivered shall be over a minimum period of twelve (12) months - as agreed to by the Mason County Road Commission and the Contractor - beginning the first month after award, then continuing until the amount is paid off.